

CONSTRUCTION NOTICE

Serving Californians Since 1929

Corryne Area Main Replacement Project Installation of New 8” Water Main, New 10” Water Main, Domestic Services, Fire Services and Fire Hydrants

What	Installation of new 450’ of new 8” PVC and 750’ of new 10” PVC Water Mains, fire hydrants, domestic and fire services in Corryne Place, Slauson Avenue, Jefferson Blvd., and Sepulveda Blvd., in The City of Culver City.
When	Construction will commence on June 18, 2018 with completion expected by August 30, 2018. The Culver City working hours are from: 8:00 am to 4:00 pm. On Corryne Place 9:00 a.m. to 3:00 p.m. on Slauson, Jefferson and Sepulveda Blvd.
Where	Corryne Place from Slauson Avenue to Sepulveda Blvd., (replace approx. 450 LF of 1929 4” CI with 8” PVC. Replace 4” CI in Slauson to alley between Jefferson Blvd, and Sepulveda Blvd., with 8” PVC, add a fire hydrant and switch existing services to surrounding existing mains. Abandon section of 1978 4” CI between Sepulveda and Jefferson Blvd., in alley south of Jefferson Blvd. Slauson Avenue from Selmaraine Drive to Sepulveda Blvd., (replace approx. 750 LF of 1929 6” CI with 10” PVC and add one additional fire hydrant).
What to Expect	Construction crews with backhoes, dump trucks, crew trucks and hand tools will be digging along the new pipeline alignment. The services will generally be installed using an air compressor and pneumatic boring tool. The streets will remain open to traffic during the construction period but traffic and parking may be restricted and access to driveways may be limited for short durations of time. The construction crews will make every effort to keep dust to a minimum. Please expect an increased level of noise during the construction period. Weekly activities such as trash pick-up will not be interrupted. As sections of the new main are completed crews will disinfect the main. This step is necessary to protect public health and to ensure compliance with the Waterworks Standards. Following the disinfection period, crews will flush the chlorinated water and any construction related sediment from the main. Crews will dechlorinate the water before discharge. Generally, as underground activities are completed the crews will progress to the next underground sections and come back near the end of the project to perform landscape and hardscape restoration as well as perform final street paving.
Contacts	If you have any questions or concerns about the construction activities for this project, please call the Golden State Water Company Customer Service Center at (800) 999-4033.

Golden State Water Company thanks you for your patience while we work to improve your water system.



At Golden State Water Company, it has been all about water for more than 80 years. Our team of professionals delivers reliable, quality water and great service to customers in 75 communities across California.

Project #23611363

Culver City Permit # U17-0169 SU 0264 CALTRANS 717-6UT-1055